www.kit.solutions



# CARPORT CUSTOM

IBIS - PVC tarpaulin

Welded and bolted structural steelwork protected with hot-dip galvanization, with "N" shaped support columns complete of base plate and accessories.

Material S235JR-S275JR-S355JR UNI EN 10025-1/2, grade 8.8 bolting material.

DELIVERY TIME: 3 WEEKS FROM EXW ORDER

VALIDITY PRICES FROM 04-2023 TO 12-2023

€ 3,050.00 VAT EXCLUDED

# **TECHNICAL SPECIFICATIONS**

5,00x5,00 m
25 m²
2,00 m
5,00 m
25 m/s
YES
PVC tarpaulin

#### **Metal Working**

Galvanized, pre-painted, shaped metal sheets for ridges, corner joints, flashings and eaves and any other necessary element.

#### **Painting**

Hot-dip galvanized coating UNI EN ISO 1461:2009.

#### Covering

Roof covering in self-extinguishing PVC coated 1100 Dtex polyester fabric, with a glossy lacquered finish on both sides.

# **OPTIONAL PRODUCTS**

#### **EV CHARGING STATION**

EV charging station with no. 2 socket outlet, floor standing, connected to the user's distribution network (optimizable with PV), complete with access badge reader, power 7kW, 32 A.

## "WIRE" SIDE CLADDING

Vegetation support made of steel cables complete with turnbuckles and stainless steel accessories.

#### "ECO-BRISE" SIDE CLADDING

Cladding made of wood-plastic composite slats.

#### "WIRE" BACK SIDE CLADDING

Vegetation support made of steel cables complete with turnbuckles and stainless steel accessories.

# "ECO-BRISE" BACK SIDE CLADDING

Cladding made of wood-plastic composite slats.

# **COLOR STRUCTURE**

# galvanization

Other colors depending on availability. The colours here shown are purely indicative and may result different in reality

## **COLOR COVERING**













ther colors depending on availability. The colours here shown are purely indicative and may result different in realit